LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

CHIPPEWA CO.

2 CORNERS

FOR CORNERS OF -:	LOCATED IN -:	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY	T44 N. R6_ W.	_B-11 ·	•
2. PROPERTY CONTROLL- ING IN SECTION—	29 ,T. 44 N. R. 6 K.	4:	
3. MISCELLANEOUS PROPERTY IN SECTION =	,TS., RW.		
4. LOT NO , R	ECORDED PLAT		
5. PRIVATE CLAIMS			REGISTER OF DEEDS STAMP AND

- A. Description of original monument and accessories and/or subsequent restoration:
- B-11 South 1/4 Corner of Section 30. 0.B.T.'S: Spruce 4", N74°W, 35 1ks. & Tamarack 3, S36°E, 28 1ks.
- 4 Northwest 1/16 Corner of Section 29. Not prev. set.
 - B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- B-11 Corner set by single proportionate measure between S.W. and S.E. Section Corners of Section 30.
- 4 Corner set at the center of Northwest 1/4 of Section 29 by closed traverse.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: DNR Monument set at both corners.

- B-11 5" Tamarack, N22^OE, 31.4' ε 5" Tamarack, S56^OE, 41.8' ε 4" Tamarack, S10^OE, 19.2' ε 4" B. Spruce, N38^OW, 17.1'.
- 4 7" Balsam, N58°E, 24.4' ε 10" Aspen, S72°E, 10.55' ε 6" Balsam, S49°E, 7.70' ε 7" Spruce, S82°W, 32.6'.

SIGNED BY Gerald L. Wiggins

DATE 9-9-86

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

23521

