

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Chippewa  
 (County)

Located In: \_\_\_\_\_ Corner Code ≠#

- |                                    |   |            |   |            |             |
|------------------------------------|---|------------|---|------------|-------------|
| 1. Public Land Survey              | T | <u>44N</u> | R | <u>6W</u>  | <u>K12</u>  |
|                                    | T | _____      | R | _____      | _____       |
|                                    | T | _____      | R | _____      | _____       |
|                                    | T | _____      | R | _____      | _____       |
| 2. Property Controlling in Section | S | <u>36</u>  | T | <u>44N</u> | R <u>6W</u> |
|                                    | S | _____      | T | _____      | R _____     |
| 3. Miscellaneous Property in Sec.  | S | _____      | T | _____      | R _____     |
|                                    | S | _____      | T | _____      | R _____     |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

7 Nov 05 2001  
 K12 Nov 08 2001

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(K12) Quarter corner common to Sections 35-36. 1981: Reestablished by Billy D. Buckler RLS midway and on a line between section corners. 1" pipe with 4" aluminum cap. 6" Spruce S15W 22.5', 8" W.Pine N22E 46.1'.  
 (7-Sec. 36) North 1/16 corner between Section 36 T44N-R06W and Section 31 T44N-R05W. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K12) Recovered the 1981 monument in good condition and at record bearing and distance from the 1981 accessories. The B.Spruce is in good condition. The W.Pine is dead but standing. Left the monument in place and made new witnesses.  
 (7-Sec. 36) Established the corner midway and on a line of mean true bearing between Section corner 1318.77' north and Quarter corner 1318.77' south. An old railroad grade is about 130' east of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K12) Fd. 1" ID iron pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:  
 8" B.Spruce S25W 22.7' (1981 wit)  
 4" B.Spruce N03W 4.8' "1/4S NBT"  
 5" J.Pine N89W 11.7' do  
 5" B.Spruce N55E 15.4' do  
 Cedar post adjacent. Bearings are magnetic. Distances to nail with tag.

(7) Set 1" IDx36" iron pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:  
 6" Balsam S81W 14.15' "N1/16 BT"  
 6" Balsam S25E 6.35' do  
 10" R.Pine N41W 36.85' do  
 12" R.Pine S44E 25.8' do  
 Cedar post adjacent. Bearings are magnetic. Distances to nail with tag.



Signed by Stephan J. Szyszkoski Date 11/28/01  
 Surveyor's Michigan License No. 33986