

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>30</u> T <u>44N</u> R <u>6W</u>	<u>10</u>
	S <u>30</u> T <u>44N</u> R <u>6W</u>	<u>12</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 26 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20 ____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (10-Sec. 30) South 1/16 corner between Section 30 T44N-R06W and Section 25 T44N-R07W. Not established in the original survey.
- (12-Sec. 30) South 1/16 corner, Section 30. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (10-Sec. 30) Established the corner midway and on the Range line between Section corner 1320.76' south and Quarter corner 1320.76' north. From the position thus established, I found a 3 ft. high metal fence post N67E, 20.6' distant, which I did not accept as marking the position of the corner.
- (12-Sec. 30) Established the corner midway and on a straight line between Center of Section 30 1317.52' north and Quarter corner 1317.52' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| (10) Set 1"IDx36" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
8" W.Pine S18W 13.5' mrkd "S1/16 BT"
10" Spruce S56E 17.63' do
12" Spruce N59E 20.92' do
12" Spruce S53W 34.78' do
Bearings are magnetic. Distances are to
nail with MDNR tag. | (12) Set 1"IDx36" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
8" Spruce S77W 59.2' mrkd "S1/16 BT"
8" twin Cherry N28E 38.29' do
7" Spruce S03E 43.69' do
6" Spruce S27E 30.8' do
Bearings are magnetic. Distances are to
nail with MDNR tag. |
|--|---|



Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11	●	●											
12	31		32		33		34		35		36		
13													

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/2/07

For the Michigan Department of Natural Resources, Office of Land and Facilities