

MAR 09 1994

Chippewa County Remonumentation Corner

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

93 DEC 29 PM 2:48

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 44N R 2E C-13
- 2. Property Controlling in Section S ___ T ___ R ___
- 3. Miscellaneous Property in Sec. S ___ T ___ R ___
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

J. Roger Malotte
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, William L. Karr, in a field survey on December 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(C-13) Standard Corner of Sections 31 and 32, (T44N-R2E)

1963: Neal Spherhake, L.S. 7876 (Kimberly Clark Corp.). The Standard Corner is called for in the corner certificate for the Closing Corner of Sections 5 and 6, T43N-R2E which is recorded in Liber 3, Page 119 of the Chippewa County Corner Records. A found iron pipe is called for at the Standard Corner position. The Closing Corner was re-established 26.40' West of the Standard Corner.

1979: Thomas M. Kelley, L.S. 24599. Corner recorded in Liber 4, Page 245 of the Chippewa County Corner Records. Found 1" pipe called for in survey by N.D. Alix, L.S. 6254. Called for Closing Corner 53' more or less to the West.

8" Poplar N36°E 75.00' Power Pole S25°E 45.60' 12" Poplar N28°W 65.65'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C-13) This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found 1½" O.D. pipe 24.88' East of the Closing Corner. Found three record witness objects (Poplar to the Northeast is dead). Found no evidence of Closing Corner as called for by Kelley. Accepted corner position as found and offset it prior to road reconstruction. Replaced corner after construction completed. Added two additional witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(C-13) Corner is a 3/4" x 12" iron with plastic "Chippewa County Remonumentation" cap. Corner falls 2.5' North of the centerline of Gogomain Road (East-West, paved). Falls on the centerline of Clay Road to the North (North-South, gravel).

Witnesses:

- "V" Notch in North End 36" C.M.P. N53°E 38.39'
- Power Pole PD2/55/72 S30°E 45.62' (existing nail & IS 24599 tag)
- 8" Aspen S14°E 68.55'
- 12" Aspen N31°W 65.45' (existing nail & IS 24599 tag)
- Closing Corner Sections 5 & 6 West 24.88'

Signed by William L. Karr Date 12/23/93
Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination.
Distances are to a nail in side of witness objects unless noted.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

