

MAR 09 1994

COMMISSION

Chippewa County Remonumentation Corner

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

LAND CORNER RECORDATION CERTIFICATE

93 DEC 29 PM 2:49

Filing Requirement of Act 74, Mich. P.A. 1970

J. Roger Malott
REGISTER OF DEEDS

For corners in
Chippewa

(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>44N</u> R <u>2E</u> | <u>D-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

I, William L. Karr, in a field survey on December 7, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(D-13) South 1/4 Corner of Section 32, (T44N-R2E)

1963: Neal Sperhake, L.S. 7876 (Kimberly Clark Corp.). Witness Corner recorded in Liber 3, Page 121 of the Chippewa County Corner Records.
Re-established corner position midway between the Southeast and Southwest corners of Section 32 and held centerline of Gogomain Road for North-South position. Corner falls 19.80' East of the North 1/4 Corner of Section 5. Set a 1" pipe with a stamped aluminum cap as a Witness Corner 33' North. Witnessed the Witness Corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
(D-13) This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a PK nail 33.05' South of record Witness Monument and 19.81' East of North 1/4 Corner of Section 5. Distance East to the Southeast corner of Section 32 is 2699.64' (Sperhake - 2668.05'). Distance West to the Southwest corner of Section 32 is 2668.24' (Sperhake - 2668.05'). Accepted corner position as found and offset prior to road reconstruction. Replaced corner after construction completed.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(D-13) Corner is a 3/4" x 24" iron with plastic "Chippewa County Remonumentation" cap. Corner Falls in centerline of Gogomain Road (East-West, paved). Falls 98' West of centerline of East Bay Road to the North (North-South, gravel).

Witnesses:

1 1/4" O.D. Pipe with Stamped Aluminum Cap	North	33.05'
Wood Sign Post	N68°E	79.69'
Power Pole	S72°E	124.88'
10" Balsam Poplar	S08°W	58.21' (Common Witness)
North 1/4 Corner of Section 5	West	19.81'

Signed by William L. Karr Date 12/29/93
Surveyor's Michigan License No. 27450

