

MAR 09 1994

Chippewa County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 29 PM 2:49

COMMISSION

For corners in
Chippewa

(County)

Located In:

Corner Code ##

- | | | |
|---------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>44N</u> R <u>2E</u> | <u>F-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

J. Roger Malott
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, William L. Karr, in a field survey on December 8, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(F-13) South 1/4 Corner of Section 33 (T44N-R2E)

1840: Corner established by Austin Burt for William A. Burt.
Set 1/4 Section Post.
11" Sugar N82°E 12 links
20" White Birch N74 1/2°W 53 links

1983: Harry W. Goodwin, L.S. 5434. Corner shown on a survey recorded in Liber 441, Page 182 of the Chippewa County Records. Survey shows corner 26.70' East of the North 1/4 corner of Section 4. Survey calls for a 1/2" rebar with cap #5434.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F-13) This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a 1/2" iron and remains of L.S. cap. Found corner falls 26.66' East of the North 1/4 corner of Section 4 (a 1/2" iron with remains of L.S. cap). Computed GLO distance is 26.73'. Accepted corner position as found and offset prior to road reconstruction. Replaced after construction completed.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(F-13) Corner is a 3/4" x 24" iron with plastic "Chippewa County Remonumentation" cap. Corner falls 1' North of the centerline Gogomain Road (East-West, paved).

Witnesses:

- | | | |
|-------------------------------|-------|--------|
| 16" Maple | N46°E | 58.89' |
| 14" Cedar | S42°E | 81.61' |
| 6" Maple | S15°W | 88.07' |
| 8" Maple | N24°W | 58.72' |
| North 1/4 Corner of Section 4 | West | 26.66' |

Signed by William L. Karr Date 12/23/93

Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination.
Distances are to a nail in side of witness objects unless noted.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

