

MAR 09 1994

Chippewa County Remonumentation Corner

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

COMMISSION

LAND CORNER RECORDATION CERTIFICATE 93 DEC 29 PM 2:49

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa

(County)

Located In:

Corner Code ##

- | | | |
|---------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>44N</u> R <u>2E</u> | <u>G-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

J. Roger Matthe
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, William L. Karr, in a field survey on December 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G-13) Standard Corner of Sections 33 & 34 (T44N-R2E)

1963: Neal Sperhake, L.S. 7876 (Kimberly Clark Corp.). Witness Corner recorded in Liber 3, Page 111 of the Chippewa County Corner Records. Re-established corner position using what he believed to be an old County Surveyor witness post (wood post scribed "33 and 34 WC"). Set a 1" pipe with stamped aluminum cap as a Witness Corner 33' North. Witnessed the Witness Corner.

1983: Harry W. Goodwin, L.S. 5434. Corner shown on a survey recorded in Liber 441, Page 182 of the Chippewa County Records.

Survey shows corner 40.20' East of the Closing Corner Sections 3 and 4. Survey calls for a 1/2" rebar with cap #5434.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G-13) This corner is being perpetuated as part of the Chippewa County Remonumentation Program.


Found a 1/2" iron with remains of L.S. cap. Found corner falls 40.12' East of the Closing Corner Sections 3 and 4 (1/2" iron with remains of L.S. cap). Did not find witness monument set by Sperhake. Accepted corner position as found and offset it prior to road reconstruction. Replaced corner after construction complete.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G-13) Corner is a 3/4" x 24" iron with plastic "Chippewa County Remonumentation" cap. Corner falls 0.5' South of centerline Gogomain Road (East-West, paved).

Witnesses:

- | | | |
|-------------------------------|-------|---------------------------------------|
| 7" Spruce | N08°E | 64.45' |
| 7" Balsam Fir | N48°E | 96.88' |
| 6" Cedar | S58°E | 69.53' |
| 5" Cedar | S38°E | 46.18' |
| 8" White Birch in Clump | S52°W | 65.22' (existing nail-common witness) |
| (Witness for Witness Corner) | | |
| Closing Corner Sections 3 & 4 | West | 40.12' |



Signed by William L. Karr Date 12/23/93

Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination.

Distances are to a nail in side of witness objects unless noted.