

SURVEY & REMONUMENTATION

MAR 09 1994

Chippewa County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
 CHIPPEWA COUNTY
 STATE OF MICHIGAN

93 DEC 29 PM 2:51

COMMISSION

For corners in

Chippewa

(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|-----------|------|
| 1. Public Land Survey | T | <u>44N</u> | R | <u>2E</u> | L-13 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

J. Roger Malott
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William L. Karr, in a field survey on December 19, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L-13) South 1/4 Corner of Section 36 (T44N-R2E)

This corner was recovered by Neal Sperhake, L.S. 7876, of the Kimberly-Clark Corp. on August 8, 1963. It was recorded in Liber 3, Page 103 of the Chippewa County Corner Records in 1977. Sperhake found an old scribed wood post which was apparently set in an 1895 survey by the County Surveyor. He also recovered what he felt to be an original Tamarack Bearing Tree the proper size and distance from the corner. He set a galvanized iron pipe, 3' long x 1" in diameter, with a "Kimberly-Clark Corp." cap.

Spruce 4 N47°E 31 links
 Tamarack 4 N28°W 30 links

Both witnesses were scribed.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L-13) This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found 1" galvanized pipe with Kimberly-Clark Corp. aluminum cap as described in Liber 3, Page 103. Accepted corner position as found and added new witnesses.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L-13) Corner is a 1" galvanized pipe with a Kimberly-Clark Corp. aluminum cap. Corner falls on an East-West brush line.

Witnesses:

4" Cedar	N52°E	22.15'
3" Tamarack	S73°E	21.61'
3" Tamarack	S13°E	7.93'
5" Tamarack	N28°W	19.94'
North 1/4 Corner Section 1	West	20.97'



Signed by William L. Karr

Date 12/23/93

Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination. Distances are to a nail in side of witness objects unless noted.