

MAR 5 1999

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**Chippewa County Remonumentation Corner**

For corners in SECTION

Chippewa County	Located in:	Corner Code #
1. Public Land Survey	T44N R2W	E-10
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

47.00 LAND CORNER  
 42.00 MSSR  
 5 MAR 1999 2:01:01 PM Receipt #14029  
 RECEIVED FOR RECORD  
 CHIPPEWA COUNTY - STATE OF MICHIGAN  
 SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 11 PAGE 14

Register of Deeds Stamp & File Number

I, Keith R. Waters, in a field survey on November 20, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-10 1/4 Corner Common to Sections 28 & 29, T44N, R2W

1845 - Original corner (8" White Pine) established by James Mullett.

1905 - Chippewa County Surveyor Frederick H. Brown, RLS 944, sketch of Section 28 shows this corner midway between section corners 2652 feet north and 2652 feet south.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being reestablished as part of the Chippewa County Remonumentation Program. Found no evidence of the original corner. Reestablished corner on line between section corners at E-9 2650.5 feet to the north and E-11 2648.9 feet to the south, on the extension of the remains of a fence line to the west.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed a 3/4" x 24" rebar with a plastic Chippewa County Remonumentation cap at the corner location, which falls approximately 4 feet east of the centerline of Centerline Road under an east-west power line. Witnesses:

- Nail and plastic witness tag #33142 in side of Power Pole, EAST 78.47'
- Nail and plastic witness tag #33142 in side of Power Pole, WEST 270.34'
- Nail and plastic witness tag #33142 in side of blazed 4" Spruce, S42°W 103.74'
- Rivet on Top of West End of 24" Culvert, N22°W 91.39'



Signed by Keith R. Waters

Date 12-30-98

Surveyor's Michigan License No. 33142