

CHIPPEWA COUNTY REMONUMENTATION CORNER

MAR 27 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in
Chippewa

Located In: Corner Code #

- | | | |
|------------------------------------|-------------------|------------|
| 1. Public Land Survey | T 44N R 2W | E-13 Same |
| | T 43N R 2W | E-1 Corner |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

\$ 7.00 LAND CORNER
\$ 2.00 HSSR
28 FEB 96 4:33 P.M. RECEIPT# 459
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Keith R. Waters 12/19 95
I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.


- A. Description of original monument and accessories and/or subsequent restoration:
E-13 Corner Common to Sections 4 & 5, T43N, R2W & Sections 32 & 33, T44N, R2W
1840 - Corner established by William A. Burt: 10" White Birch for Corner.
1845 - Witnesses added by James Mullett during the subdivision of T43N, R2W: Birch 6, S21°W 10 links - Birch 8, S86°W 21 links.
1971 - Mary C. Feindt, P.S. 3920, Mackinac County LCRC A-73, shows found 2" iron pipe at corner.
1987 - Richard L. Hays, P.S. 25847, Mackinac County LCRC C-354, found 1 1/2" well point as recovered by Ray Walker and Mary Feindt.
Set 2 1/2" x 3' monument with 3" aluminum cap at corner location.
1987 - Richard L. Hays, P.S. 25847, Mackinac County LCRC D-31, revised witnesses shown in LCRC C-354.
1993 - David B. Guthrie, P.S. 22435, Mackinac County Remonumentation Surveyor, Mackinac County LCRC D-206, found pipe w/cap.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.
Found a 2 1/2" x 3' monument with a 3" aluminum cap stamped to identify the corner. Also found all witness objects as called for in 1993 Mackinac County LCRC.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 2 1/2" x 3' monument with a stamped 3" aluminum cap in the ditch on the east side of north-south gravel road (Bay/Centerline Road). Witnesses:
8" Balsam Poplar, S80°E 38.72' (With bearing tree tag)
8" Balsam Poplar, N80°E 37.98' (With bearing tree tag)
8" Ash, N69°W 58.71' (With bearing tree tag)
6" Cherry, S61°W 95.65' (With bearing tree tag)
6" Spruce, S15°W 35.00' (Blazed and painted)
Post, EAST 1.65'



Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date December 29, 1995