

1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Chippewa County Remonumentation Corner

For corners in

Table with columns: Chippewa County, Located in:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

\$7.00 LAND CORNER
\$2.00 MSSR
5 MAR 1999 2:08:50 PM Receipt #14029
RECEIVED FOR RECORD
CHIPPewa COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 11 PAGE 25
Register of Deeds Stamp & File Number

I, Keith R. Waters, in a field survey on November 12, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column G and row 6.

A. Description of original monument and accessories and/or subsequent restoration:

G-6 1/4 Corner Common to Sections 15 & 16, T44N, R2W

1845 - Original corner (6" Spruce) established by James Mullett.

1897 - Chippewa County Surveyor Frederick H. Brown, RLS 944, notes for Section 15 show the west line with distances of 2646 feet for the north 1/2 mile and 2642 feet for the south 1/2 mile.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program. Found a 1/2" rebar 3 feet west of the centerline of Hantz Road, on the extension of a field line to the east. Found rebar is midway on line between section corner G-5 to the north and G-7 to the south. Accepted corner as found.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a 1/2" rebar at the corner location, which falls 3 feet west of the centerline of Hantz Road, on the extension of a field line to the east. Witnesses:

- Nail and plastic witness tag #33142 in side of Power Pole (22), S10°W 265.68'
Nail and plastic witness tag #33142 in side of blazed 14" Spruce, S02°E 742.92'
Nail and plastic witness tag #33142 in side of Power Pole (RU2/24A/26), N04°E 637.92'
Nail and plastic witness tag #22428 in side of Power Pole, N10°W 134.28'



Signed by Keith R. Waters

Date 12-30-98

Surveyor's Michigan License No. 33142