

CHIPPEWA COUNTY REMONUMENTATION CORNER

MAR 27 1996

LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey

T 44N R 2W

H-13 Same
H-1 Corner

T 43N R 2W

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

\$ 7.00 LAND CORNER

\$ 2.00 MSSR

28 FEB 96 4:33 P.M. RECEIPT# 459

RECEIVED FOR RECORD

CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Keith R. Waters

12/19

95

I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-13 1/4 Corner Common to Section 3, T43N, R2W & Section 34, T44N, R2W
1840 - Original ties (William A. Burt): Cedar 6, N03°W 14 links - Fir 6, N38°W 14 links.

Found no evidence of subsequent restoration of this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being re-established as part of the Chippewa County Remonumentation Program. Re-established corner by single proportionate measurement on the township line between recovered corners at the S.E. and S.W. corners of Section 34, T44N, R2W. The S.W. corner of Section 34, T44N, R2W was re-established in 1971 by Mary C. Feindt, P.S. 3920, by single proportionate measurement between recovered corners at the S.W. corner of Section 33 and the S.E. corner of Section 34, T44N, R2W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4" x 24" rebar with a stamped 3" aluminum Chippewa County Remonumentation cap. Witnesses:

- 8" Black Ash, S49°W 20.06'
- 12" Red Maple, S75°W 48.22'
- 6" Black Ash, N30°E 24.55'
- 8" Black Ash, S08°E 36.52'

Note: Distances are to a nail/tag P.S. 33142 in the side of the tree. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date December 29, 1995

