

APR 26 1995

CHIPPEWA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa

	(County)	Located In:	Corner Code ##
1. Public Land Survey		T 44N R 2W	L-1 Same
		T 45N R 2W	L-13 Corner
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____

\$ 7.00 LAND CORNER
 \$ 2.00 MSSR
 19 JAN 95 4:19 P.M. RECEIPT# 2266
 RECEIVED FOR RECORD
 CHIPPEWA COUNTY - STATE OF MICHIGAN
 SHARON H. KENNEDY, REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Keith R. Waters in a field survey on December 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-13 1/4 Corner Common to Section 1, T44N, R2W & Section 36, T45N, R2W.

Original notes indicate a 6" diameter fir for 1/4 section corner.

Found no evidence of subsequent restoration of this corner.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 (T45N, R2W)
 This corner is being re-established as part of the Chippewa County Remonumentation Program.
 Found no evidence of corner. Re-established corner by single proportionate measurement on township line mid-way between township corner 2633.27 feet east and common section corner 2633.27 feet west.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 (T45N, R2W)
 Corner is a 3/4" x 48" rebar with 3 1/4" aluminum Chippewa County Remonumentation cap. Witnesses:

- | | |
|-------------------------|---|
| 9" Spruce, N53°W 5.24' | Note: Distances are to a nail in the side of the tree. Trees are blazed and painted. Bearings are compass bearings corrected for declination. |
| 7" Spruce, S19°W 18.14' | |
| 5" Spruce, SOUTH 23.25' | |
| 8" Spruce, S66°E 28.60' | |

Signed by Keith R. Waters Date 12-23-94

Surveyor's Michigan License No. 33142