

MAR 18 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Chippewa County Remonumentation Corner

For corners in SECTION

Chippewa County	Located in:	Corner Code #
1. Public Land Survey	T44N R2W	A-4 } Same
	T44N R3W	M-4 } Corner ✓
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No.	Recorded Plat	
5. Private Claims		

\$7.00 LAND CORNER
\$2.00 MSSR
5 MAR 1999 10:36:49 AM Receipt #1401
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds, Map & File Number

I, Keith R. Waters, in a field survey on June 30, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-4 1/2 Corner Common to Section 7, T44N, R2W & Section 12, T44N, R3W

- 1840 - Original corner established by William A. Burt.
Witnesses: Fir 6, S41 1/2°W 43 links - Cedar 10, N69°W 38 links.
- 1908 - Chippewa County Surveyor Frederick H. Brown, RLS 944, notes for Section 7 show this corner midway between section corners 2640 feet north and 2640 feet south.
- Circa 1972 - Certificate of Survey by Harry W. Goodwin, RLS 5434, shows this corner as a set 1/2" iron with cap #5434. A distance of 2640 feet is shown to an existing section corner to the north. No witness objects are shown.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program. Found a bent 1/2" rebar with remains of a plastic cap in the approximate centerline of a north-south dirt road, on the extension of old fence lines to the east and west. The distance to the section corner A-3 to the north is 2640.2 feet. Accepted the corner position as found and replaced the bent 1/2" rebar with a 3/4" rebar and plastic Chippewa County Remonumentation cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced a found bent 1/2" rebar with a 3/4" x 24" rebar and plastic Chippewa County Remonumentation cap at the corner location, which falls in the approximate centerline of Turner Road, on the extension of fence lines east and west. Witnesses:

- Nail and plastic witness tag #33142 in side of blazed 10" Scotch Pine, N59°E 111.60'
- Nail and plastic witness tag #33142 in side of blazed 6" Spruce, N73°E 33.21'
- Nail and plastic witness tag #33142 in side of blazed 5" Balsam Fir, S73°W 48.46'
- Nail and plastic witness tag #33142 in side of blazed 4" Balsam Fir, S18°W 31.01'

Signed by Keith R. Waters

Date 12-30-98

Surveyor's Michigan License No. 33142

