

MAY 28 1997

COMMISSION

CHIPPEWA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE #7.00 LAND CORNER
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa (County)	Located In:	Corner Code #
1. Public Land Survey	T44N R 5W	F-11
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

\$2.00 MSSR
2/28/1997 4:00:38 PM Receipt #226
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 9 PAGE 386

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Keith R. Waters, in a field survey on 09/09, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-11 1/4 Corner Common to Sections 28 & 33, Town 44 North, Range 5 West

1849 - Original ties (Harvey Mullen): Sugar 18, S48°E 32 links - Sugar 16, N41°W 04 links.

1937 - United States Department of Interior, General Land Office, Dependent Resurvey, Oscar Walsh, surveyor.

Found an old wood stake. Mr. Louis Decap, County Commissioner, states that the post is a perpetuation of the original corner location. Bearing trees were destroyed by road construction. Placed a 2" x 36" monument with brass cap.

Witnesses: 6" Maple, N28°25'E 164 links - 8" Maple, S02°56'E 191 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a brass capped GLO monument at the intersection of Vertz Road east-west and Lake Road to the north. Found no evidence of the previous witness objects. Accepted corner as found and established new witness objects.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a GLO monument with a brass tablet 2 feet north of the centerline of Vertz Road, 11 feet west of the centerline of Lake Road to the north. Witnesses:

Power Pole (EK3-263-8), S46°E 51.48'

Power Pole (EK3-263-7), S81°W 204.02'


10" Red Pine, N55°W 65.34'

16" Red Pine, N14°W 86.72'

Note: Unless noted otherwise, distances are to a nail/tag #33142 in the side of the witness object. Bearings are compass bearings corrected for declination. Trees are blazed and painted.

Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 12-30-96



BOOK 9 PAGE 386