

SURVEY & REMONUMENTATION

MAY 28 1997

CHIPPEWA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa (County)	Located In:	Corner Code #
1. Public Land Survey	T44N R 5W	G-9
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

\$7.00 LAND CORNER

\$2.00 MSSR

2/28/1997 4:02:50 PM Receipt #226

RECEIVED FOR RECORD

CHIPPEWA COUNTY - STATE OF MICHIGAN

SHARON H. KENNEDY REGISTER OF DEEDS

BOOK 9 PAGE 387

BOOK 9 PAGE 387

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Keith R. Waters, in a field survey on 09/09, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-9 Corner Common to Sections 21, 22, 27, & 28, Town 44 North, Range 5 West

1849 - Original ties (Harvey Mullen): Yellow Birch 8, S70°E 15 links - Hemlock 16, N43°W 16 links.

1937 - United States Department of Interior, General Land Office, Dependent Resurvey, Oscar Walsh, surveyor.

Placed corner at intersection of fence line at centerline of State Highway 48. Original corner and bearing trees were destroyed during road construction. Mr. Robert McMillan, landowner, states this is original corner location.

1961 - Jerome B. Seward, Highway Department project engineer. Found 1" iron pin and raised with a 3/4" square rod.


Witnesses: 9" Balsam, N02°E 70.92' - 15" Spruce, N52°E 66.40' - 12" Poplar, S34°W 55.12' - 4" Poplar, S17°E 44.88'

Corner is 14 feet north of the centerline of bituminous road.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a 3/4" square iron rod, 11.5 feet north of the centerline of east-west asphalt road (H-40). Location fits well with other recovered corners as shown in above mentioned dependent resurvey. Accepted corner as found and established witness objects.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4" square iron rod 11.5 feet north of the centerline of H-40.

Witnesses:

5" Cedar, N22°W 28.40'

4" Spruce, N14°E 26.82'

6" Spruce, N55°E 38.56'

7" Diameter Scribed Wood Post, S04°W 41.59' (nail with Highway Department tag in side)



Note: Unless noted otherwise, distances are to a nail/tag #33142 in the side of the witness object. Bearings are compass bearings corrected for declination. Trees are blazed and painted.

Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 12-30-96