

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
CHIPPEWA COUNTY  
STATE OF MICHIGAN

94 JUL 22 AM 11:05

*J. Roger Malott*  
REGISTER OF DEEDS

For corners in  
Chippewa  
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>45N</u> R <u>1W</u>	<u>M-4</u> Same
	T <u>45N</u> R <u>1E</u>	<u>A-4</u> Corner
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Keith R. Waters, in a field survey on OCTOBER 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
(M-4) East 1/4 Corner of Section 12, (T45N-R1W)

Original Notes: W.A. Burt, August 2, 1840, Set Quarter Section post.  
 Cedar 10" S19°W 28 links Spruce 8" N51°W 52 links  
 L.R. Rogers, 1986: Set 1/2" x 18" iron with cap # 29251. (L.6, P. 362)  
 Power Pole (DR2/111) S86°E 70.45'  
 Power Pole S64°W 95.45'  
 1/2" Iron in Monument Box South 111.00'  
 Centerline Gravel Drive to the West South 78.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M-4) Found corner and all accessories as recorded in Liber 6, Page 362 of the Chippewa County Records. Accepted corner position as found.

SURVEY &  
REMONUMENTATION

JUL 26 1994

COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M-4) Corner is a 1/2" x 18" iron with L.S. cap #29251 in a monument box in the centerline of Highway M-129.

Witnesses:

Power Pole (DR2/111)	S86°E	70.45'
Power Pole	S64°W	95.45'
1/2" Iron in Monument Box	South	111.00'
Centerline Gravel Drive to the West	South	78.00'

Signed by Keith R. Waters Date 7-22-94

Surveyor's Michigan License No. 33142

548-00

NOTE: Bearings are compass bearings corrected for declination.  
Distances are to a nail in side of witness objects unless noted.