

MAR 09 1994

CHIPPEWA COUNTY REMONUMENTATION CORNER

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 30 PM 2:43

J. Roger Malick
REGISTER OF DEEDS

For corners in
Chippewa
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>45N</u> R <u>1E</u>	C-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Keith R. Waters in a field survey on December 2, 19 93
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-1 Corner Common to Sections 5 & 6, on North Boundary of T45N, R1E
(Closing Corner on Township Line)

Original ties to post: White Pine 20, S18°E 48 links
White Pine 24, S41°W 19 links



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1 (T45N, R1E)
This corner is being perpetuated as part of the Chippewa County Remonumentation Program.
Found a 1/2" iron with cap #29251 1.8 feet north of centerline of 12 Mile Road, approximately 6 feet east of centerline of gravel road to south (Seymour Road). Also found a PK nail at standard corner 15.18 feet west, at a fence line to the north. Record GLO falling is 23 links (15.18 feet). Position also matches old County Surveyor notes. Corner is on line between standard section corners on Township line 5245.22 feet east and 15.18 feet west. Accepted corner as found. (Replaced PK nail at standard corner with a 3/4" rebar and plastic Chippewa County Remonumentation cap).

Description of monument for corner and accessories established to perpetuate locating the position of the corner: 12/30/93

C-1 (T45N, R1E)
Corner is a 1/2" iron with cap #29251 1.8 feet north of centerline of east-west asphalt road (12 Mile Road), 6 feet east of centerline of gravel road (Seymour Road) to the south. Witnesses:

- 6" Spruce, S27°W 156.04'
- Power Pole (DR2-91-14), S25°E 58.84'
- Telephone Pole (M-73), N74°E 142.72'
- Corner Fence Post, N12°W 51.63'
- 3/4" Rebar, WEST 15.18'
- (Std. Cor. Secs. 31-32, T46N, R1E)

Note: Distances are to a nail and tag in the side of witness object. Spruce is blazed and painted. Bearings are compass bearings corrected for declination.

Surveyed by Keith R. Waters

Date 12-30-93

Surveyor's Michigan License No. 33142