

CHIPPEWA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
CHIPPEWA COUNTY

93 DEC 30 PM 2:45

J. Roger Malott
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in
Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey	T	45N	R	1E	D-7
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Keith R. Waters November 23 93

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
D-7 1/4 Corner Common to Sections 17 & 20, T45N, R1E

Original ties to post: Fir 6, N67°W 14 links
Fir 6, S35°E 09 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-7 (T45N, R1E)
This corner is being perpetuated as part of the Chippewa County Remonumentation Program.
Found a 1/2" iron pin with smashed plastic cap (appears to be #27450, William L. Karr) in approximate centerline of east-west asphalt road (15 Mile Road) at the intersection of fence lines north and south. Corner is 2645.11 feet from Section corner west and 2640.71 feet from Section corner east, and is 2.23 feet south of a straight line between said Section corners. Accepted corner position as found. Replaced smashed cap with new cap #33142 and established witness objects.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-7 (T45N, R1E)
Corner is a 1/2" iron pin with cap #33142 in centerline of 15 Mile Road at fence lines north and south. Witnesses:

Power Pole, N15°E 51.40'
Corner Fence Post, S02°W 48.40'
3" Spruce, S47°W 80.40'
Fence Post, N40°W 66.07'

Note: Distances are to a nail and tag in the side of witness object. Spruce is blazed and painted. Bearings are compass bearings corrected for declination.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7		●											
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Waters
12/30/93

Signed by Keith R. Waters

Date 12-30-93

Surveyor's Michigan License No. 33142