

MAR 09 1994

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 30 RECEIVED FOR RECORD  
CHIPPEWA COUNTY  
STATE OF MICHIGAN

For corners in CHIPPEWA  
COMMISSION  
(County)

Located In: Corner Code =#

- 1. Public Land Survey T 45N R 1E E-1
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*J. Roger Malick*  
93 DEC 30 PM 2:43  
REGISTER OF DEEDS  
*J. Roger Malick*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Keith R. Waters, in a field survey on December 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1 Corner Common to Sections 4 & 5, on North Boundary of T45N, R1E (Closing Corner on Township Line)

Original ties to post: Maple 10, S60°E 16 links  
Hemlock 10, S05°W 19 links

1985 - Corner recorded by Larry R. Rogers, P.S. 29251, in liber 6, page 286, Chippewa County corner records as a ½" iron with cap 7.92 feet east of standard corner, on Township line.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1 (T45N, R1E)

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a ½" iron pin with plastic cap #29251 1.7 feet north of the centerline of east-west asphalt road (12 Mile Road) at the intersection of gravel road (Shunk Road) north-south. Corner is 7.92 east of found 1" iron pipe at standard corner for sections 32 & 33, T46N, R1E. Record GLO falling is 12 links (7.92'). Corner is on line between said standard corner and common corner 5286.29 feet east. Accepted corner as found and established new witness objects as necessary.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1 (T45N, R1E)

Corner is a ½" iron pin with cap #29251 1.7 feet north of centerline of 12 Mile Road at the intersection of Shunk Road. Witnesses:

- Power Pole (DR1-76-43), N29°W 59.67'
- 4" Spruce, S55°W 62.68'
- 12" Spruce, S29°E 92.18'
- SW Cor. Hse. Foundation, N57°E 146.56'
- 1" Iron Pipe, WEST 7.92'
- (Standard Corner Secs. 32-33, T46N, R1W)

Note: Distance to pole and trees is to a nail and tag in the side. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

Date 12-30-93

Surveyor's Michigan License No. 33142

