

SURVEY & REMONUMENTATION

APR 07 1998

SECTION

Chippewa County Remonumentation Corner LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Chippewa</u>	Located In:	Corner Code #	
1. Public Land Survey	T <u>45N</u> R <u>1E</u>	<u>E-4</u>	
	T ___ R ___		
	T ___ R ___		
	T ___ R ___		
2. Property Controlling in Section	S ___ T ___ R ___		
	S ___ T ___ R ___		
3. Miscellaneous Property in Sec.	S ___ T ___ R ___		
	S ___ T ___ R ___		

\$7.00 LAND CORNER
\$2.00 NSSR
14 Jan 1998 3:29:46 PM Receipt #5566
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK **10** PAGE **120**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		●	9		10		11		12	
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Larry R. Rogers, in a field survey on October 22, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E-4) 1/4 Corner Common to Sections 8 and 9, T.45 N., R.1 E.

Original corner post was placed in September, 1845 by James H. Mullett. Found no information in County Surveyor records about this corner. In September, 1990 Ronald Bischer, P.S. 22428, found a 3/4" iron pin and filed L.C.R.C. in Liber 7, Page 246 of the Chippewa County Corner Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E-4) 1/4 Corner Common to Sections 8 and 9, T.45 N., R.1 E.

This corner is being re-established as part of the Chippewa County Remonumentation Program.

Found 3/4" iron with bent top and recovered Bischer witnesses. Corner falls on North margin of Spruce/Cedar swamp. Accepted corner position as found and established two new witnesses. Corner falls 15.6' East of a straight line between Northwest and Southwest corners of Sections 9 and 8 1/2' South of a split.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-4) 1/4 Corner Common to Sections 8 and 9, T.45 N., R.1 E.

Corner is a 3/4" iron pin with bent top, on North margin of swamp.

Witnesses:	8" Sugar Maple	S70°W	16.95'
	10" Sugar Maple	N72°E	20.35'
	13" White Birch	S87°E	48.00'
	14" White Spruce	S04°W	34.90'
	Steel fence post	North	2.0'



Signed by [Signature] Date 19 DEC 1997

Surveyor's Michigan License No. 29251

NOTE: All bearings are compass bearings. All distances are to a nail in side of witness objects unless noted.