

**SURVEY & REMONUMENTATION**

PR: 12/12/97

**APR 07 1998**

**SECTION**

**Chippewa County Remonumentation Corner  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Chippewa</u>	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>1E</u>	<u>E-6</u>
	T ___ R ___	
	T ___ R ___	
	T ___ R ___	
2. Property Controlling in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	

\$7.00 LAND CORNER  
\$2.00 MSSR  
14 Jan 1998 3:34:56 PM Receipt #5566  
RECEIVED FOR RECORD  
CHIPPewa COUNTY - STATE OF MICHIGAN  
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK **10** PAGE **122**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Larry R. Rogers, in a field survey on October 22, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(E-6) 1/4 Corner Common to Sections 16 and 17, T.45 N., R.1 E.

Original corner post was placed in September, 1845 by James H. Mullett. 1921 County Surveyor notes indicate that 1/4 corner was set from an original B.T. and was 7.5 feet North of an even split. A 1996 survey by Ronald Bischer, P.S. 22428, found no evidence of the original corner position, and re-established the corner midway and on-line between the Northeast and Southeast corners of Section 17. Corner falls on the extension of an old fence line to East.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E-6) 1/4 Corner Common to Sections 16 and 17, T.45 N., R.1 E.

This corner is being re-established as part of the Chippewa County Remonumentation Program.


Found no evidence of original corner position. Found Bischer roerod 1 foot East of centerline of Shunk Road, on the extension of a very old fence to the East and 26 feet South of a fence line to the West. Landowners indicate fence to West was built as a containment fence and was not intended to be on East-West 1/4 line. They also believe the fence to the East is on the East-West 1/4 line. Accepted corner position as found, even though County Surveyor notes indicate the corner to be 7.5 feet farther North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-6) 1/4 Corner Common to Sections 16 and 17, T.45 N., R.1 E.

Corner is a 1/2" roerod 1 foot East of the centerline of Shunk Road and on the extension of a very old fence to the East.

Witnesses:	Fence post with tag No. 22428	N36°E	32.27'
	8" Aspen with tag No. 22428	N55°E	24.49'
	10" Aspen	S48°E	35.71'
	Fence post with tag No. 22428	N59°W	18.92'



Signed by [Signature] Date 19 DEC 1997

Surveyor's Michigan License No. 29251

NOTE: All bearings are compass bearings. All distances are to a nail in side of witness objects unless noted.