

MAR 09 1994

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 30 PM 2:43

For corners in CHIPPEWA COMMISSION

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>1E</u>	<u>F-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*J. Roger Malick*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Keith R. Waters in a field survey on December 16, 19 93  
 I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

F-1 (T45N, R1E) North 1/4 Corner of Section 4, T45N, R1E  
 Corner was not set in original survey.

Corner recorded in liber 6, page 285, of Chippewa County corner records by Larry R. Rogers, P.S. 29251 (1985), as a 1/2" iron with cap 1.5 feet north of centerline of road. Witnesses: 4" Spruce, S28°E 46.93'  
 Power Pole (DR1-76-51), S48°W 73.91'  
 SE Corner of House, N28°W 107.71'

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1 (T45N, R1E)  
 This corner is being perpetuated as part of the Chippewa County Remonumentation Program.  
 Found a 1/2" iron with plastic cap #29251 (Larry R. Rogers) 1.5 feet north of centerline of east-west asphalt road (12 Mile Road) at a fence line to the south. Distances to two remaining witnesses (power pole and house) from previous recording check well. Corner is on line between common section corner 2649.02 feet east and closing section corner 2637.27 feet west. (Closing section corner is on line between standard section corner west and common section corner east). Accepted corner as found and established new witness objects.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1 (T45N, R1E)  
 Corner is a 1/2" iron pin with plastic cap #29251 1.5 feet north of centerline of 12 Mile Road, at a fence line to the south. Witnesses:

- SE Corner of House Foundation, N28°W 107.71'
- Power Pole (DR1-76-51), S48°W 73.91'
- 4" Spruce, N59°E 79.40'
- 7" Jack Pine, S03°E 73.39'
- 3/4" Rebar, EAST 1.92'
- (S 1/4 Cor. Sec. 33, T46N, R1E)

Note: Unless noted otherwise, distances are to a nail and tag in the side of the witness object. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

Recorded by Keith R. Waters  
 Surveyor's Michigan License No. 33142

Date 12-30-93

