

SURVEY & REMONUMENTATION

APR 07 1998

SECTION

Chippewa County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa

Located In:

Corner Code #

1. Public Land Survey

T 45N R 1E

G-6

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling in Section

S ___ T ___ R ___

S ___ T ___ R ___

3. Miscellaneous Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Larry R. Rogers, in a field survey on October 22, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, *monumented*, *recovered*, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G-6) 1/4 Corner Common to Sections 15 and 16, T.45 N., R.1 E.

Original corner post was placed in September, 1845 by James H. Mullett. County Surveyor records recite conflicting distances from 1/4 corner to Section corner to South (2606 and 2626). A 1996 recorded survey by Ronald Bischer, P.S. 22428, indicates a 1/2" iron pin 33.00' West of a fence corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G-6) 1/4 Corner Common to Sections 15 and 16, T.45 N., R.1 E.

This corner is being re-established as part of the Chippewa County Remonumentation Program.

Found 1/2" iron pin from Bischer survey. Corner is 33.0' West of a corner fence post, 1' East of centerline of Ridge Road, 1.7' North of the extension of the fence to east, is on line between Section corners to North and South and within 0.4' of a split of the distance between said Section corners. Accepted corner position as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G-6) 1/4 Corner Common to Sections 15 and 16, T.45 N., R.1 E.

Corner is a 1/2" iron pin, 1' East of the centerline of Ridge Road.

Witnesses:	Corner fence post	S89°E	33.06'
	4" White Spruce	N22°E	122.14'
	4" Balsam Fir	N82°W	24.91'
	16" Willow	N26°W	53.27'
	Utility pole	West	50.83'

47.00 LAND CORNER
 42.00 NSSR
 14 Jan 1998 3:41:14 PM Receipt #5566
 RECEIVED FOR RECORD
 CHIPPEWA COUNTY - STATE OF MICHIGAN
 SHARON H. KENNEDY, REGISTER OF DEEDS

 BOOK 10 PAGE 129

 Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													



Signed by [Signature]

Date 19 Dec 1997

Surveyor's Michigan License No. 29251

NOTE: All bearings are compass bearings. All distances are to a nail in side of witness objects unless noted.