

CHIPPEWA COUNTY REMONUMENTATION CORNER

MAR 09 1984

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in CHIPPEWA (County)

Located in: Corner Code #/

- 1. Public Land Survey T 45N R 1E H-7
- 2. Property Controlling in Section S \_\_\_ T \_\_\_ R \_\_\_
- 3. Miscellaneous Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_
- 4. Lot No. \_\_\_ , Recorded Plat \_\_\_
- 5. Private Claims

RECEIVED FOR RECORD  
CHIPPEWA COUNTY

93 DEC 30 PM 2:46

*J. Roger Malott*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number



	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters in a field survey on November 24, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 H-7 1/4 Corner Common to Sections 15 & 22, T45N, R1E  
 Original ties to post: Sugar 10, S45°W 24 links Aspen 19, S14°E 19 links  
 This corner is recorded in liber 6, page 16, of Chippewa County corner records by James L. Fletcher, P.S. 19830 (1982), as a set 1/2" rerod with cap. No indication is given as to how corner was established.  
 Witnesses: Anchor Pole, N42°W 29.05' Power Pole, S10°W 82.73'  
 Center of Creek, WEST 314' Centerline of Road, SOUTH 34.4'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 H-7 (T45N, R1E)  
 This corner is being perpetuated as part of the Chippewa County Remonumentation Program.  
 Found a 1/2" iron pin with cap #19830 34.4 feet north of centerline of east-west asphalt road (15 Mile Road). Distance to Section corner east is 2632.01 feet and distance to Section corner west is 2631.85 feet. Corner is 103.07 feet north of a straight line between said Section corners, which is consistent with County Surveyor notes dating back to 1921. Accepted corner location as found and replaced 1/2" iron with a 3/4" rebar and 3 1/4" aluminum Chippewa County Remonumentation cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 H-7 (T45N, R1E)  
 Corner is a 3/4" x 24" rebar with 3 1/4" aluminum Chippewa County Remonumentation cap 34.4 feet north of centerline of 15 Mile Road. Witnesses:  
 Anchor Pole, N45°W 28.90'  
 Power Pole, S11°W 82.90'  
 5" Spruce, N83°W 132.65'  
 5" Spruce, S13°E 79.60'

Note: Distances are to a nail and tag in the side of witness object. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

signed by Keith R. Waters Date 12-30-93  
Surveyor's Michigan License No. 33142