

SURVEY &
REMONUMENTATION

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

Chippewa County Remonumentation Corner

MAR 09 1994

LAND CORNER RECORDATION CERTIFICATE 93 DEC 29 AM 10:27
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION
Chippewa
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>45N</u> R <u>1E</u> | <u>I-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

J. Roger Malott
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Larry R. Rogers, in a field survey on November 12, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration
(I-11) Section Corner Common to Sections 26, 27, 34 & 35, T45N-R1E


Corner position was restored in 1984 by D.B. Babbitt (M.D.N.R.) and recorded in Liber 6, Page 165 of Chippewa County Corner Records as a 1" iron pipe with plastic R.L.S. cap in centerline of Riverside Drive, with the following witnesses:

- | | | |
|--------------|-------|--------|
| Fence Corner | S78°W | 51.35' |
| Power Pole | N74°W | 47.60' |
| Fence Corner | S61°E | 59.00' |
| Fence Post | S40°E | 73.30' |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I-11) This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found 1" pipe with remains of plastic cap in centerline of Riverside Drive, 4' North of centerline of old road bed to the East and 20' North of fence line to the East. Corner position matches three remaining witnesses from 1984 record. Established two new witnesses.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I-11) Corner is a 1" iron pipe in the centerline of Riverside Drive.

- | | | |
|---------------------------------------|-------|---------|
| Witnesses: Utility Pole (DR2/190A/18) | N75°W | 47.54' |
| Utility Pole | S62°W | 124.83' |
| Fence Post | S40°E | 73.25' |
| Gate Post | S60°E | 62.03' |
| Corner Fence Post (leaning) | S68°E | 59.33' |



Signed by *Larry R. Rogers* Date 30 NOV 1993
Surveyor's Michigan License No. 29251

NOTE: Bearings are compass bearings corrected for declination.
Distances are to a nail in side of witness objects unless noted.