

REMONUMENTATION

MAR 09 1994

COMMISSION

CHIPPEWA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
CHIPPEWA COUNTY  
STATE OF MICHIGAN

93 DEC 30 PM 2:43

*J. Roger Malott*  
REGISTER OF DEEDS

For corners in  
Chippewa  
(County)

Located In:	Corner Code #
T 45N R 1E	J-1 Same
T 46N R 1E	J-13 Corner
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

Lol No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Keith R. Waters in a field survey on December 2, 1993, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

J-1 (T45N, R1E)  
1/4 Corner Common to Section 2, T45N, R1E & Section 35, T46N, R1E.

Original ties to post: Cedar 12, N65°E 10 links  
Fir 6, N13°W 09 links

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1 (T45N, R1E)  
This corner is being perpetuated as part of the Chippewa County Remonumentation Program.  
Found a 1/2" iron pin with cap #33142 (Keith R. Waters) in centerline of east-west gravel road (12 Mile Road) at the centerline of a ditch to the south and at remains of a fence line to the north. Corner is mid-way on line between Section corners 2646.05 feet east and 2646.05 feet west. Position also fits well with north-south fences at 1/16 lines one quarter mile east and west. Accepted corner as found and established witness objects.



Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1 (T45N, R1E)  
Corner is a 1/2" iron pin with cap #33142 in centerline of 12 Mile Road at the centerline of a ditch to the south. Witnesses:

- 7" White Oak, N03°W 52.24'
- 22" Spruce, N51°E 63.28'
- 14" White Birch, S77°E 111.13'
- Power Pole (DR1-76E-15), S74°W 132.23'

Note: Distances are to a nail and tag in the side of the witness object. Trees are blazed and painted. Bearings are compass bearings corrected for declination. Distances measured with EDM.

Recorded by Keith R. Waters

Date 12-30-93

Surveyor's Michigan License No. 33142