

REMONUMENTATION CHIPPEWA COUNTY REMONUMENTATION CORNER

MAR 09 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

For corners in CHIPPEWA
COMMISSION
(County)

Located In: Corner Code #

93 DEC 30 PM 2:46

- | | | |
|---------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T 45N R 1E | J-7 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

J. Roger Mabele
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Keith R. Waters, in a field survey on November 24, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
J-7 1/4 Corner Common to Sections 14 & 23, T45N, R1E
Original corner was a 12" Maple.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
J-7 (T45N, R1E)
This corner is being perpetuated as part of the Chippewa County Remonumentation Program.
Found a 1/2" iron pin with plastic cap #29251 (Larry R. Rogers) in a monument box 0.5 feet north of centerline of east-west asphalt road (15 Mile Road) at the centerline of a farm lane to the south. Distance to Section corner east is 2708.68 feet and distance to Section corner west is 2707.17 feet. Corner is 1.55 feet north of a straight line between said Section corners. Accepted corner as found and established witness objects.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
J-7 (T45N, R1E)
Corner is a 1/2" iron pin with cap #29251 in a monument box 0.5 feet north of the centerline of Riverside Drive. Witnesses:

- Gate Post, S07°E 44.56'
- Power Pole, S37°W 59.25'
- Concrete Monument w/cap #29251, NORTH 49.99'
- 9" Spruce, N65°E 107.28'

Note: Distances to post, pole, and spruce are to a nail with tag #29251 in the side. Spruce is blazed and painted. Bearings are compass bearings corrected for declination.

W. Kam
12/30/93

Signed by Keith R. Waters Date 12-30-93
Surveyor's Michigan License No. 33142