

MAR 09 1994

CHIPPEWA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
CHIPPEWA COUNTY  
STATE OF MICHIGAN

93 DEC 30 PM 2:46

*J. Roy Malick*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

COMMISSION

or corners in  
Chippewa

Located In:	Corner Code #
T 45N R 2E	A-7 Same
T 45N R 1E	M-7 Corner
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

Keith R. Waters, in a field survey on November 29, 1993

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

A-7 Corner Common to Secs. 13 & 24, T45N, R1E & Secs. 18 & 19, T45N, R2E

Original ties to post: Birch 12, N64°E 38 links Sugar 10, S51°W 57 links

This corner is recorded in liber 1, page 208, Chippewa County corner records by Neree D. Alix, R.L.S. 6254 (1976), as a 1" pipe re-established from ties as found in Chippewa County Surveyor's office. Record ties:  
32" Maple, N05°E 145.00' Fence Line, WEST 24.0' Utility Pole, N57°E 68.6'  
Utility Pole, S42°E 75.2' West Range of House, EAST 108.0'

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7 (T45N, R2E)

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a 1/2" iron pin with plastic cap #27450 (William L. Karr) in a monument box 3.2 feet south of centerline of east-west asphalt road (15 Mile Road). Also found three witness objects with nail and cap #27450 in sides. Power pole northeast of corner appears to be the same as in previous recording and checks well. Accepted corner as found.



Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7 (T45N, R2E)

Corner is a 1/2" iron with cap #27450 in a monument box 3.2 feet south of the centerline of 15 Mile Road. Witnesses:

- Power Pole (DR2-223), S25°E 62.02'
- Power Pole (DR2-223-A), N56°E 68.60'
- Power Pole, N34°W 65.79'
- 10" Maple, S15°W 77.18'

Note: Distances are to a nail and tag in the side of witness object. Maple is blazed and painted. Bearings are compass bearings corrected for declination.

by Keith R. Waters

Date 12-30-93

Surveyor's Michigan License No. 33142