

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Chippewa Co.

2 Corners

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. R. 1 E.	K-12, I-9
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-6 & 6-21, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

K-12 West 1/4 Corner of Section 36. Wood Post. OBT'S: Cedar 9, N57⁰W, 14 lks. & Birch 4, S66⁰E, 15 lks.

I-9 N.W. Section Corner of Section 26. Wood Post. OBT'S: B. Ash 10, N41⁰E, 8 lks. & Fir 10, S69⁰W, 21 lks. Co. Surveyor F. Brown about 1925 no description of monument given. 16" S. Maple, N29¹/₂⁰W, 130.5' & Pole, N19⁰E, 80' & Pole, S7¹/₂⁰E, 109'.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

K-12 Set M.P.O.L. between the N.W. Section Corner and the S.W. Section Corner of Sec. 36.

I-9 Set from stump of Co. Surveyor F. Browns N.W. N.B.T. A 23" S. Maple, N29¹/₂⁰W, 130.5'. Corner falls in center line of N-S blacktop road and in line with a graded road East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12 D.N.R. Monument. Bearings: 12" Aspen, S25⁰W, 44.1' & 6" R. Maple, S6⁰W, 56.7' & 8" Cedar, S55⁰E, 57.4' & 12" Aspen, N46⁰E, 43.7'.

I-9 1" pipe W/plastic RLS Cap buried in center line of North and South Road. Bearings: 14" Aspen, S50⁰W, 96.9' & 5" Spruce, S88⁰W, 69.05' & Tag in Power Pole, N40⁰W, 57.25' & Tag in Power Pole, N57⁰E, 55.35' & 16" Maple Stump, N29⁰W, 130.5'.

SIGNED BY

David B. Babbitt
David B. Babbitt

DATE 9-17-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: