

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Chippewa Co.

3 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. S. R. 1 E. W.	K-11, L-11
2. PROPERTY CONTROLLING IN SECTION	25 T. 45 N. S. R. 1 E. W.	15
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-2 & 7-3, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- K-11 S.W. Section Corner of Section 25. Wood Post. OBT'S: Hemlock 10, N81°W, 08 lks.
Cedar 10, S71°E, 08 lks.
- L-11 South 1/4 Corner of Section 25. Wood Post. OBT'S: Hemlock 8, S49°E, 05 lks.
Hemlock 12, N49°W, 21 lks.
- 15 West 1/16 Corner on South Section Line of Section 25. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-11 Found old post point in center line of abandoned road grade west and in line with an old fence running Northerly. I presume this to be the location of the corner described in the County Surveyors record dated 1907 in which he states that he ran the South line of sec. 26 "for highway on S. line" and that the original bearing trees for the S.E. Sec. Cor. were standing at the time of his survey. He does not note any N.B.T.'S.
- L-11 Corner set M.P.O.L. between S.W. Sec. Cor. and S.E. Sec. Cor. of Section 25. Could not identify anything for OBTS at this time.
- 15 Corner set M.P.O.L. between the S.W. Sec. Cor. and the South 1/4 Cor. of Sec. 25.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D.N.R. Monument set at all three corners. Bearings:
- K-11 14" Spruce, N72°W, 55.6' & 5" Tamarack, N63°W, 32.6' & 16" Tamarack, N30°E, 13.0' & 7" Spruce, S85°E, 53.5'.
- L-11 12" Aspen, East, 14.6' & 8" Balsam, S31°E, 21.3' & 10" Aspen, S28°W, 19.4' & 8" Aspen, S70°W, 15.7'.
- 15 12" H. Maple, S63°E, 94.21' & 12" H. Maple, N77°E, 44.22' & 14" H. Maple, N31°E, 123.05' & 7" Aspen, N16°E, 118.54'.

SIGNED BY

David B. Babbitt

DATE 9-14-84

David B. Babbitt

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)