

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Chippewa Co.

2 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. S. R. 1 E. W.	M-11, J-13
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-2, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- M-11 S.E. Section Corner of Section 25. Wood Post. OBT'S: Spruce 10, S69°W, 07 lks, and Spruce 8, N1°W, 14 lks. By Co. Surveyor Frederic Brown about 1925. 1" X 30" Deformed Iron Bar North of 3" X 3" Cedar Post. Witt: W. Birch 10", N60°W, 23.8', Balsam 7", S40°W, 32.0', Balsam 6", S30°E, 23.0', and W. Birch 10", N30°E, 31.5'.
- J-13 South 1/4 Corner of Section 35. Wood Post. OBT'S: Hemlock 15, N35°E, 35 lks. Hemlock 18, N53°W, 29 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- M-11 Set by single proportion between the East 1/4 corner of sec. 25 and the S.E. Sec. cor. of Sec. 36. Found 1" Deformed Iron set by County Surveyor Brown N25°E, 67' from this point. By his own statement he did not use the proper method to set his iron bar. Mr. Brown states that he could not find the original corner location so he set his iron 2640 South of the East 1/4 cor. of sec. 25 with out reference to any other corner. This is obviously not the correct procedure. I could not find any evidence of the original gov't survey either so have set this sec. cor. by single proportion as prescribed for Twp. Lines.
- J-13 Set M.P.O.L. between the S.E. and S.W. section corners of section 35.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-13 D.N.R. Monument. Bearing: J-13 1" pipe W/Plastic RLS Cap buried in road.
- | | |
|------------------------------------|---|
| 20" Cedar, S84°E, 12.6' | 7" H. Maple, S52°W, 28.7' |
| 14" Cedar, S40°W, 10.1' | 6" Cherry, N05°W, 31.1' |
| 16" Cedar, S80°W, 8.0' | 7" Spruce, N36°E, 40.5' |
| 10" Cedar, N37°W, 7.6' | 12" Spruce, S10°W, 30.8' |
| 1" Deformed Iron Bar, N25°E, 67.0' | 10.57' East to North 1/4 Cor. of Sec.2, T44N R1E. |

SIGNED BY

David B. Babbitt
David B. Babbitt

DATE 9-13-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)