

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --	Chippewa Co. LOCATED IN --	3 Corners. CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. X , R. 1 E. X	M-12, M-13
2. PROPERTY CONTROLLING IN SECTION	36, T. 45 N. X , R. 1 E. X	14
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ S., R. _____ E. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-6, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- M-12 East 1/4 Corner of Section 36. Wood Post. OBT'S: Birch 7, S36°W, 18 lks.,
Birch 6, N24°W, 35 lks.
- M-13 S.E. Section Corner of Section 36. Wood Post. OBT'S: Birch 6, S38°E, 42 lks.,
B. Ash 8, N66°W, 11 lks. A 4" Pipe filled W/Conc. set by C.M. Cade in 1930. NBT'S:
Post, S44°E, 36.0'.
- 14 South 1/16 Corner on east side of Section 36. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- M-12 Set M.P.O.L. between the N.E. and S.E. Section Corners of Section 36.
- M-13 Found Cades monument frost heaved out of ground and had been broken - presumably by road equipment. Replaced broken monument with 1" pipe and plastic cap.
- 14 Set M.P.O.L. between the East 1/4 Corner and the S.E. Section Corner of Section 36.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-12 D.N.R. Monument. Bearings: 16" Tamarack, N65°E, 41.45' & 6" Twin R. Maple, N26°E, 20.7' & 5" Balm, N11°W, 15.4' & 8" R. Maple, S76°W, 20.4'.
- M-13 1" Pipe W/plastic R.L.S. Cap. Bearings: 6" Tamarack, S28°E, 70.4' & 6" Tamarack, S21°E, 68.1' & 8" Aspen, S19°W, 95.3' & Sq. Post, North, 6.0'.
- 14 D.N.R. Monument. Bearings: 8" Spruce, S68°W, 12.4' & 8" W. Birch, West, 27.3' & 9" Tamarack, N20°W, 17.2' & 5" Spruce, N66°E, 13.1'.

SIGNED BY

David B. Babbitt
David B. Babbitt

DATE 9-17-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)