

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Chippewa Co.

3 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 45 N. <del>S.</del> , R. 1 E. <del>W.</del>	M-10, K-10
2. PROPERTY CONTROLLING IN SECTION 25	T. 45 N. <del>S.</del> , R. 1 E. <del>W.</del>	14
3. MISCELLANEOUS PROPERTY IN SECTION	T. S., R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- M-10 East 1/4 Corner of Section 25. Wood Post. OBT'S: Sugar 20, S34°W, 35 lks. & Maple 18, N60°W, 22 lks. Co. Surveyor F. Brown about 1925. New Cedar Post South of old one. 24" Maple (Orig. BT), S30°W, 23' & 36" Y. Birch, N30°E, 116.2' & 12" Maple, S10°E, 42'.
- K-10 West 1/4 Corner of Section 25. Wood Post. OBT'S: Hemlock 12, S45°E, 13 lks. and Fir 8, N80°W, 22 lks.
- 14 South 1/16 Corner on East side of Section 25. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- M-10 Found 1" Iron Bar with the original Sugar B.T. alive and standing (now 36"), S34°W, 23.1' Brown's N.E. N.B.T. is alive and standing. Brown's S.E. N.B.T. is down and badly rotted.
- K-10 Set from remains of Hemlock stump presumed to be the S.E. O.B.T. County Surveyors records dated 1904 to 1907 indicate both O.B.T'S. were in place at that time. The land was being occupied and fenced at that time also. This corner falls in line with a faint road grade west and the N. 1/16 corner position falls in an old road grade north from that point and in line with an old fence west.

- 14 Corner set M.P.O.L. between East 1/4 corner and S.E. section corner of section 25.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-10 1" Re-Bar. Bearings: 10" R. Maple, N81°E, 29.3' & 4" R. Maple, N30°W, 13.95' & 6" R. Maple, South, 43.7' & 36" H. Maple, (Original), S34°W, 23.1'.
- K-10 D.N.R. Monument. Bearings: 8" W. Birch, N23°W, 29.8' & 8" Cedar, S55°E, 4.9' & 5" Cedar, S47°W, 22.7' & 6" Cedar, S16°W, 26.2'.
- 14 D.N.R. Monument. Bearings: 8" W. Birch, N8°W, 10.2' & 7" Aspen, N80°E, 23.0' & 6" Spruce, S33°E, 29.2' & 9" Aspen, S19°W, 11.3'.

SIGNED BY

*David B. Babbitt*

DATE 9-17-84

David B. Babbitt  
SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)