

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Chippewa Co.

3 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. _____ N. _____ S., R. _____ E. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION <u>26</u>	T. <u>45</u> N. _____ S., R. <u>1</u> E. _____ W. _____	<u>16, 14, 13</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S., R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-11 & 7-25, 19 84, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 16 East 1/16 Corner on South side of Section 26. Not prev. set.
- 14 South 1/16 Corner on East side of Section 26. Not prev. set.
- 13 S.E. 1/16 Corner of Section 26. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 16 Set M.P.O.L. between the South 1/4 Corner and S.E. Section Corner of Section 25.
- 14 Set M.P.O.L. between the S.E. Section Corner and the East 1/4 Corner of Section 26.
- 13 Set at the computed center of the S.E. 1/4 of Section 26.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D.N.R. Monument set at all three corners. Bearings:

- 16 7" Aspen, N82°W, 55.4' & 7" Aspen, N66°W, 27.5' & 7" Aspen, N30°W, 21.8' & 6" Aspen, N23°E, 12.7'.
- 14 10" Aspen, S16°E, 98.7' & Tag in Fence Post, S15°W, 86.0' & 8" Aspen, S27°W, 96.2' & 6" Balsam, S38°W, 100.6'.
- 13 Tag in Fence Post, S64°W, 62.0' & Tag in Fence Post, S37°W, 41.4' & Tag in Fence Post, S3°E, 37.6' & Tag in Fence Post, S38°E, 53.2'.

SIGNED BY

David B. Babbitt
David B. Babbitt

DATE 9-17-84

SURVEYOR'S MICHIGAN REGISTRATION NO.

21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: