

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 Chippewa

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>1E</u>	<u>E8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	4	5	6	7	8	9	10	11	12	13	14	15	16
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	10	11	12	13	14	15	16	17	18	19	20	21	22
7													
8	13	14	15	16	17	18	19	20	21	22	23	24	25
9													
10	16	17	18	19	20	21	22	23	24	25	26	27	28
11													
12	19	20	21	22	23	24	25	26	27	28	29	30	31
13													

I, Stephan J. Szyszkoski, in a field survey on September 15, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E8) Quarter corner common to Sections 20-21. Corner established in 1845 by James H. Mullett as follows: "A sugar 8 in. in diam. for quarter section corner." Original notes show section corners 40.00 ch. north and south. Found no subsequent record. (Part B continued from below)... I reestablished the corner in the center of the old road bed, as best as could be determined, and equidistant between perpetuated original section corners 2637.60' north and south. At the position for the corner, I placed a 1"x36" iron pipe capped with a yellow plastic cap stamped "Mich DNR LS 33986".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E8) Original corner tree not recovered. The corner falls in a N-S lane separating two cleared fields. Nathaniel Armstrong and Bernard Doll, both life-time residents of this area and land owners in sections 20 and 21, both admitted to me in July 1993 that they have never seen nor heard of a monument at this corner, nor know of its existence. Two old N-S fence lines run roughly parallel to the lane on the east and west, neither run in a straight line but meander and jog. Mr. Armstrong told me that the lane was one of the first Co. roads to be built in this area, that it existed before 1906, and was constructed prior to 15 Mile Rd. It once extended southerly to the SW corner of Sec. 21, a perpetuated original corner. Mr. Armstrong stated that the fence lines bordering the lane were moved in the 1960's to accommodate school bus passage and that the location of the fences, to his knowledge, were positions of convenience, and that "nobody worried if the fences were on the line or not". Although the road to the north and the remains of the road to the south are not perfectly straight, the general trend clearly indicates that the road approximates a line between the section corners having an angle point at the quarter corner location. The road bed itself is the oldest recovered evidence of the position of the original corner and is accepted as such. (Continued under Part A. above...)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E8) Set 1" pipe with plastic cap.
 Set measuring nails with tags in the following accessories:
 wood fence post S75W 9.9'
 wood fence post S40W 16.6'
 wood fence post N30W 27.5'
 6" Spruce N60E 40.6'
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 1-25-94