

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa

(County)

Located In:

Corner Code -##

- 1. Public Land Survey T 45N R 1E E7
- T R
- T R
- T R
- 2. Property Controlling in Section S T R
- S T R
- 3. Miscellaneous Property in Sec. S T R
- S T R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on July 21, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(E7) Corner common to Sections 16-17-20-21. Original corner established in 1845 by James H. Mullett. Original Bts: Fir 8 S43E 11, Cedar 10 N43W 20. Field notes of former Chippewa Co. Surveyor F.H. Brown, dated July, 1903 show "An original U.S. Cor" here and the following accessories (which are F.H. Browns possibly ca. 1920's.): NW 41' fence cor., N34E 48.5' Elm 8, S58 1/2W 59.5' Elm 6, SE 40.5' fence cor., SE 37' small boulder, north 32' E-W range of fence, West 29' range of fence north, West 26.5' range of fence south, East 30' range of fence south, East 74' range of west side school bldg., North 64' range of south side school bldg., N52E to SW cor school. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E7) original post and accessories not recovered. Corner falls in the paved surface of 15 Mile Rd. in a fill. Remonumented the corner at the original position as determined from the remains of the 1926 accessories: the old school building, now abandoned and decrepit, and the small boulder, apparently undisturbed. The fences all appear to have been constructed subsequent to Brown's record and do not check. Fences to the NE and SE are non-existent. A shed was added to the south side of the school after Brown witnessed the corner. At the position for the corner, I drove a 1"x36" iron pipe capped with a yellow plastic cap stamped "MICH OHR LS 33986". From the corner monumented, I found a PX nail in the center of 15 mile road surfacing 1.35' north and 0.2' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E7) 1" iron pipe with plastic cap
Distances to the following bearing objects are to nails set in plastic caps stamped LS 33142. Bearings magnetic.
Power pole N20W 56.4'
corner fnc post (fnc S&W) S38W 58.8'
corner fnc post (fnc N&E) N70E 131.45'
post marking telephone riser S26E 52.55'



Signed by Stephan J. Szyszkoski Date 1-25-94
Surveyor's Michigan License No. 33986