

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>26</u> T <u>45N</u> R <u>01E</u>	<u>16</u>
	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

I, Stephan J. Szyszkoski, in a field survey on July 24, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(16-Sec. 26) East 1/16 between Sections 26 and 35. 1984 - Established by D.B.Babbitt RLS midway and on line between Section corner to east and Quarter corner to west. Set DNR monument. 7" Aspen N82W 55.4', 7" Aspen N66W 27.5', 7" Aspen N30W 21.8', 6" Aspen N23E 12.7'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(16) The 1984 monument was recovered in good condition, at record bearing and distance from the 1984 witness trees, now all either cut down or dead standing. Accepted the monument as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(16) Fd. 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nails with MDNR tags in the following trees:

- 5" Birch S08W 3.55' mrkd "E1/16 BT"
- 6" Maple S55W 28.45' do
- 5" Maple N37E 15.25' do
- 6" Birch N87W 31.5' do

Bearings are magnetic. Distances are to nail with tag in the side of the tree.



Signed by Stephan J. Szyszkoski Date 9/11/07

Surveyor's Michigan License No. 33986