

SURVEY & REMONUMENTATION

APR 26 1995

CHIPPEWA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in
Chippewa
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|--------------------------|-------------------|
| 1. Public Land Survey | T <u>45N</u> R <u>1W</u> | <u>A-3</u> Same |
| | T <u>45N</u> R <u>2W</u> | <u>M-3</u> Corner |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |

\$ 7.00 LAND CORNER
\$ 2.00 MSSR
5 DEC 94 12:35 P.M. RECEIPT# 1520
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Keith R. Waters in a field survey on November 12, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-3 Corner Common to Secs. 6 & 7, T45N, R1W & Secs. 1 & 12, T45N, R2W.

Original ties to post: Birch 12, S26°W 16 links
Cedar 12, N49°W 13 links

Found no evidence of subsequent restoration of corner.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-3 (T45N, R1W)

This corner is being re-established as part of the Chippewa County Remonumentation Program.

Found no evidence of corner or its accessories. Re-established corner by single proportionate measurement on range line between Southwest corner of Section 18, T45N, R1W to the south and Northwest corner of Section 6, T45N, R1W (Township corner) to the north.

Note: A galvanized pipe bearing N39°E 49.9 feet from set corner was found. It was set by landowner in the NW¼ of NW¼ of Section 7, T45N, R1W, who told me that he set the pipe merely as an approximation of his corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3 (T45N, R1W)

Corner is a 3/4" x 24" rebar with 3/4" aluminum Chippewa County Remonumentation cap. Witnesses:

- 7" Spruce, N72°E 25.92'
- 9" Spruce, S57°E 9.85'
- 6" Red Maple, N86°W 16.70'
- 7" Tamarack, N25°W 31.96'

Note: Distances are to a nail and tag in the side of the tree. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

Date 12-1-94

Surveyor's Michigan License No. 33142

