

**SURVEY & REMONUMENTATION**

CHIPPEWA COUNTY REMONUMENTATION CORNER

APR 26 1995

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners of **COMMISSION**  
**Chippewa**

(County)

Located In:

Corner Code #

1. Public Land Survey

T 45N R 1W  
T 45N R 2W

A-5 Same  
M-5 Corner

T R

T R

2. Property Controlling in Section

S T R  
S T R

3. Miscellaneous Property in Sec.

S T R  
S T R

\$ 7.00 LAND CORNER

\$ 2.00 HSSR

5 DEC 94 12:35 P.M. RECEIPT# 1520

RECEIVED FOR RECORD

CHIPPEWA COUNTY - STATE OF MICHIGAN  
SHARDN H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters, in a field survey on November 12, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

A-5 Corner Common to Secs. 7 & 18, T45N, R1W & Secs. 12 & 13, T45N, R2W.

Original notes indicate Tamarack 4 for Section corner.

Witnesses: Tamarack 8, S40°E 02 links

Tamarack 10, N16°W 13 links

Found no evidence of subsequent restoration of corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-5 (T45N, R1W)

This corner is being re-established as part of the Chippewa County Remonumentation Program.

Found no evidence of corner or its accessories. Re-established corner by single proportionate measurement on range line between Southwest corner of Section 18, T45N, R1W to the south and Northwest corner of Section 6, T45N, R1W (Township corner) to the north. Corner falls approximately 250 north of the south side of a large marsh area.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5 (T45N, R1W)

Corner is a 3/4" x 48" rebar with 3 1/4" aluminum Chippewa County Remonumentation cap on the south side of a large marsh area. Witnesses:

- 8" Spruce, S23°E 251.48'
- 10" Spruce, S16°E 252.46'
- 7" Spruce, S09°E 253.25'
- 8" Spruce, S01°E 240.70'

Note: Distances are to a nail and tag in the side of the tree. Trees are blazed and painted. Bearings are compass bearings corrected for declination.



Signed by Keith R. Waters

Date 12-1-94

Surveyor's Michigan License No. 33142

