

SURVEY & REMONUMENTATION

CHIPPEWA COUNTY REMONUMENTATION CORNER

APR 26 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in
Chippewa

	(County)	Located In:	Corner Code #
1. Public Land Survey	T 45N R 1W	A-9	Same
	T 45N R 2W	M-9	Corner
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			



\$ 7.00 LAND CORNER
\$ 2.00 HSSR
19 JAN 95 4:04 P.M. RECEIPT# 2266
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON W. KENNEDY, REGISTER OF DEEDS
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, Keith R. Waters in a field survey on December 8, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-9 Corner Common to Secs. 19 & 30, T45N, R1W & Secs. 24 & 25, T45N, R2W.

Original ties to post: Tamarack 10, N70°W 26 links, Tamarack 6, N15°E 24 links
1973 - Corner position is shown in LCRC recorded in liber 1, page 129, by Lawrence Feindt, P.S. 21566. Corner mathematically placed by single proration between East 1/4 corner Sec. 25 and Northeast Cor. Sec. 24.
1978 - LCRC recorded in liber 1, page 368, Thomas Kelly, RLS 24599. Established corner by single proportionate measurement using same corners as shown in LCRC above. Set cedar post in swamp and witness monument.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-9 (T45N, R1W)

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.
Found a cedar post in swamp and a concrete witness monument 233.98 feet to the south on township line as called for in liber 1, page 368. Witness monument is on the north side of an east-west 2-track road running along power lines. Also found two witness objects as called for in liber 1, page 368. Accepted corner position as found and established additional witnesses to witness monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9 (T45N, R1W)

Corner is a 3" diameter cedar post in swamp. A concrete witness monument with 1/2" iron and cap on township line is 233.98 feet south. Witnesses to monument:

- 5" Spruce, S07°W 65.55'
- 7" White Pine, S09°E 73.15'
- Power Pole, S70°E 140.77'
- 15" White Pine, N67°W 59.85'

Note: Distances to spruce and 7" white pine are to a nail and tag in the side. Distances to pole and 15" white pine are to a PK nail and cap #24599 in the side. Trees are blazed and painted. Bearings are compass bearings corrected for declination.



Signed by Keith R. Waters Date 12-23-94
Surveyor's Michigan License No. 33142