

SURVEY & REMONUMENTATION

APR 26 1995

CHIPPEWA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Chippewa

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>1W</u>	<u>B-9</u>
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		



\$ 7.00 LAND CORNER
\$ 2.00 MSSR
19 JAN 95 4:10 P.M. RECEIPT# 2266
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9	●												
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters, in a field survey on December 6, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-9 1/4 Corner Common to Sections 19 & 30, T45N, R1W.

Original ties to post: Hemlock 16, S44°E 06 links Hemlock 18, N13°E 22 links
1991 - As recorded in liber 7, page 335, Chippewa County corner records, by Keith Waters, P.S. 33142. Set 1/2" iron with cap by single proportionate measurement between section corners east and west. Witnesses:
9" Red Pine, S83°E 16.73' 12" Red Pine, SOUTH 13.72'
12" Red Pine, S80°W 27.35' 12" Red Pine, N28°E 25.04'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


B-9 (T45N, R1W)
This corner is being perpetuated as part of the Chippewa County Remonumentation Program.
Found a 1/2" iron with plastic cap #33142 and all four bearing trees as called for in liber 7, page 335. I established this corner in 1991 by single proportionate measurement between section corners 2681.67 feet east and 2616.21 feet west. Corner falls towards the northwest corner of a finger of high ground covered predominantly by white birch and red pine, with swamps to the north, south, and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-9 (T45N, R1W)
Corner is 1/2" iron with plastic cap #33142. Witnesses:

- 10" Red Pine, S83°E 16.73'
- 13" Red Pine, SOUTH 13.72'
- 13" Red Pine, S80°W 27.35'
- 13" Red Pine, N28°E 25.04'

Note: Distances are to a nail in the side of the tree. Trees are blazed and painted. Bearings are compass bearings corrected for declination.



Signed by Keith R. Waters Date 12-23-94
Surveyor's Michigan License No. 33142