

SURVEY & REMONUMENTATION

CHIPPEWA COUNTY REMONUMENTATION CORNER

APR 26 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa

(County)

Located In: Corner Code #

- | | | |
|---------------------------------------|--------------------------|------|
| 1. Public Land Survey | T <u>45N</u> R <u>1W</u> | B-13 |
| | T _____ R _____ | |
| | T _____ R _____ | |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |



\$ 7.00 LAND CORNER
\$ 2.00 MSSR
24 OCT 94 3:46 P.M. RECEIPT# 831
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters, in a field survey on June 20, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-13 South 1/4 Corner of Section 31, T45N, R1W

Original ties to post: 8" Hemlock, N14°E 27 links
6" Spruce, N31°W 28 links

1978 - Corner recorded in liber 1, page 365, Chippewa County corner records, T. Kelly, RLS 24599. Set concrete monument. Witnesses: Corner Post, N38°E 43.13' - 6" Maple, S50°W 33.18' - 6" Pine, N10°W 19.21'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13 (T45N, R1W)

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a 4" diameter concrete monument on the south side of an old wood post. Distances to witness objects from 1978 records check well. Corner was established by single proportionate measurement on the township line between township corner to the west and corner common to Sections 33 & 34, T45N, R1W, and Sections 3 & 4, T44N, R1W to the east. Accepted corner as found and established new witness objects.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13 (T45N, R1W)

Corner is 4" diameter concrete monument on the south side of an old wood post. Witnesses:

- 6" Red Maple, S48°W 33.06'
- 10" Red Pine, N07°W 19.14'
- 9" Spruce, N61°E 7.71'
- 5" Spruce, S62°E 20.54'

Note: Distances are to a nail and tag in the side of the witness object. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 10-18-94

