

SURVEY & REMONUMENTATION

CHIPPEWA COUNTY REMONUMENTATION CORNER

APR 26 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**
Chippewa

Located In: _____ Corner Code # _____

(County) _____

1. Public Land Survey T 45N R 1W E-13
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____



\$ 7.00 LAND CORNER
 \$ 2.00 HSSR
 24 OCT 94 3:47 P.M. RECEIPT# 831
 RECEIVED FOR RECORD
 CHIPPEWA COUNTY - STATE OF MICHIGAN
 SHARON H. KENNEDY, REGISTER OF DEEDS
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters in a field survey on June 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 E-13 Corner Common to Sections 32 & 33, on South Boundary of T45N, R1W.
 (Standard Corner on Township Line)
 Original ties to post: Sugar, N38°W 06 links (No diameter indicated)
 Fir 4, N69°E 17 links (No diameter indicated)
 1978 - Corner recorded in liber 1, page 356, Chippewa County corner records, T. Kelly, RLS 24599. Set concrete monument. Witnesses: 8" White Birch, N70°E 21.46' - 6" Jack Pine, S29°W 23.68' - 10" Maple, N38°W 6.70'
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 E-13 (T45N, R1W)
 This corner is being perpetuated as part of the Chippewa County Remonumentation Program.
 Found a 4" diameter concrete monument and jack pine bearing tree from previous recording. Also found remains of stumps from other two bearing trees. Corner was established by single proportionate measurement on the township line between township corner to the west and common corner to Sections 3 & 4, T44N, R1W and Sections 33 & 34, T45N, R1W to the east. Corner falls approximately 230 feet north of an east-west 2-track road. Accepted corner as found and established new witness objects.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 E-13 (T45N, R1W)
 Corner is 4" diameter concrete monument approximately 230 feet north of an east-west 2-track road. Witnesses:

- 12" White Pine, S56°W 11.06'
- 8" Jack Pine, S28°W 23.67'
- 10" White Pine, N09°W 25.86'
- 12" White Pine, S83°E 35.20'

Note: Distances are to a nail and tag in the side of the witness object. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters
 Surveyor's Michigan License No. 33142

Date 10-18-94

