

SURVEY & REMONUMENTATION

APR 26 1995

CHIPPEWA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa
(County)

Located In: Corner Code #

- 1. Public Land Survey T 45N R 1W G-7
- 2. Property Controlling in Section S ___ T ___ R ___
- 3. Miscellaneous Property in Sec. S ___ T ___ R ___
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____



\$ 7.00 LAND CORNER
\$ 2.00 MSSR
5 DEC 94 12:34 P.M. RECEIPT# 1520
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters in a field survey on July 20, 1994
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-7 Corner Common to Sections 15, 16, 21, & 22, T45N, R1W.

Original ties to post: Hemlock 12, N30°W 12 links
Spruce 12, S28°E 20 links
1958 - As recorded in liber 3, page 29, Chippewa County corner records by Billy Buckler, RLS 8887. Set 1" pipe w/brass cap.
Witnesses: 10" Tamarack, S35°E 82½ links
12" White Birch, S33°W 32 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-7 (T45N, R1W)
This corner is being perpetuated as part of the Chippewa County Remonumentation Program.
Found a ½" solid iron rod approximately 50 feet south of an east-west path. Also found blazed 15" tamarack and blazed 16" white birch bearing trees as called for in liber 3, page 29. Corner was established in 1958 by Billy Buckler, using section corner 1 mile south, 1/4 corner 1½ miles east, and County Surveyor ties to old Mackinac Trail to the west. It appears corner was to have been monumented with a 1" pipe and Department of Conservation cap, but that did not happen. Accepted corner position as found and replaced ½" iron with a 3/4" rebar and aluminum Chippewa County Remonumentation cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7 (T45N, R1W)
Corner is a 3/4" x 24" rebar with 3¼" aluminum Chippewa County Remonumentation cap 50 feet south of an east-west trail. Witnesses:

- 15" Tamarack, S35°E 55.10'
- 16" White Birch, S33°W 20.35'
- 8" Tamarack, EAST 18.37'
- 6" Spruce, N14°E 22.81'

Note: Distances are to a nail and tag in the side of the tree. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

Date 12-1-94

Surveyor's Michigan License No. 33142

