

SURVEY & REMONUMENTATION

APR 26 1995

CHIPPEWA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa
(County)

Located In: Corner Code #

- 1. Public Land Survey T45N R 1W H-13
T ___ R ___
T ___ R ___
T ___ R ___
- 2. Property Controlling in Section S ___ T ___ R ___
S ___ T ___ R ___
- 3. Miscellaneous Property in Sec. S ___ T ___ R ___
S ___ T ___ R ___
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____



\$ 7.00 LAND CORNER
\$ 2.00 MSSR
24 OCT 94 3:48 P.M. RECEIPT# 831
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters in a field survey on May 25, 19 94
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13 South 1/4 Corner of Section 34, T45N, R1W

Original ties to post: Sugar 20, N47°E 20 links
Sugar 10, N53°W 23 links

Found no evidence of subsequent restoration of corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 (T45N, R1W)

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a 1/2" iron in the approximate centerline of an east-west dirt road, on the extension of a fence line to the north. Iron is 2639.80 feet from common section corner to the west and 2644.47 feet from standard section corner to the east, and is 0.74 feet south of a straight line between said section corners. Accepted corner as found, replaced 1/2" iron with a 3/4" rebar with a plastic Chippewa County Remonumentation cap, and established witness objects.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 (T45N, R1W)

Corner is a 3/4" x 24" rebar with a plastic Chippewa County Remonumentation cap in the centerline of an east-west dirt road on the extension of a fence line to the north. Witnesses:

- Corner Fence Post, NORTH 26.94'
- 8" Red Pine, S43°E 75.96'
- 10" Red Pine, S13°E 47.60'
- 14" Red Pine, S44°W 78.17'

Note: Distances are to a nail and tag in the side of witness object. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

Date 10-18-94

Surveyor's Michigan License No. 33142

