

SURVEY & REMONUMENTATION

CHIPPEWA COUNTY REMONUMENTATION CORNER

APR 26 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners by **COMMISSION**

Chippewa
(County)

Located In:

Corner Code ##

1. Public Land Survey	T <u>45N</u> R <u>1W</u>	<u>J-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

\$ 7.00 LAND CORNER
\$ 2.00 MSSR
5 DEC 94 12:27 P.M. RECEIPT# 1518
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Handwritten: T 45N R 1W

I, William L. Karr, in a field survey on October 28, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J-1) North 1/4 Corner Section 2, T.45 N., R.1 W.

Not set in original survey.

1901: County Surveyor notes show the North line of Section 2 as measuring 5268' (5270.26' today).

1988: L.R. Rogers set a 1/2"x 24" iron w/cap No. 29251 for the North 1/4 Corner of Section 2 on the extension of a fenceline to the South and on the Township line.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


(J-1) This corner is being perpetuated as part of the Chippewa County Remonumentation program.

Found a 1/2" iron w/cap No.29251 on the extension of a North-South 1/4 line fence in Section 2. Corner falls 16.27' East of the South 1/4 corner of Section 35, (GLO is 17.49'). Accepted corner position as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J-1) Corner is a 1/2" iron with cap No. 29251 and falls 11.4' North of the centerline of 12 Mile Road.

Witnesses: 5" Spruce	N33°E	11.55'
Fence Post	S33°E	40.71'
Fence Post	S32°W	42.51'
P.Pole(DR4/39C/19N)	N41°W	48.87'
South 1/4 corner Section 35	West	16.27'



Signed by William L. Karr Date 12/2/94

Surveyor's Michigan License No. 27450

723-12

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

**NOTE: Bearings are compass bearings corrected for declination.
Distances are to a nail in side of witness objects unless noted.**