

**SURVEY &
REMONUMENTATION**

CHIPPEWA COUNTY REMONUMENTATION CORNER

APR 26 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **CHIPPEWA**
Commission

| | | |
|---------------------------------------|--------------------------|---------------|
| | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>45N</u> R <u>1W</u> | <u>J-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

\$ 7.00 LAND CORNER
\$ 2.00 MSSR
5 DEC 94 12:33 P.M. RECEIPT# 1520
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS
Register of Deeds Stamp & File Number

I, Keith R. Waters in a field survey on November 8, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-13 South 1/4 Corner of Section 35, T45N, R1W

Original ties to post: Hemlock 18, N33°E 25 links
Hemlock 18, N67°W 32 links

Found no evidence of subsequent restoration of this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13 (T45N, R1W)

This corner is being re-established as part of the Chippewa County Remonumentation Program.

Found no evidence of corner. Re-established corner by single proportionate measurement on township line between standard section corner common to Sections 34 & 35, T45N, R1W to the west and the township corner to the east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 (T45N, R1W)

Corner is a 3/4" x 24" rebar with 3/4" aluminum Chippewa County Remonumentation cap. Witnesses:

- 10" Hemlock, N36°E 19.35'
- 14" Yellow Birch, N86°E 6.27'
- 7" Balsam Fir, S34°E 14.68'
- Twin 14" Red Maple, S62°W 22.37'
- 3/4" Rebar w/aluminum cap at North 1/4 Cor. Sec. 2, T44N, R1W, EAST 10.89'

Note: Distances are to a nail and tag in side of tree. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |



Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 12-1-94

