

**SURVEY &  
REMONUMENTATION**

**CHIPPEWA COUNTY REMONUMENTATION CORNER**


APR 26 1995

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**  
Chippewa

(County)	Located In:	Corner Code ##
1. Public Land Survey	T 45N R 1W	L-3
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		



\$ 7.00 LAND CORNER  
\$ 2.00 MSSR  
24 OCT 94 3:50 P.M. RECEIPT# 831  
RECEIVED FOR RECORD  
CHIPPEWA COUNTY - STATE OF MICHIGAN  
SHARON H. KENNEDY, REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters in a field survey on February 23, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

L-3 1/4 Common to Sections 1 & 12, T45N, R1W

Original ties to post: White Pine 20, S67°E 10 links  
Spruce 8, N38°E 11 links

1965 - The line between Sections 1 & 12 is shown in liber 2, page 220, of Chippewa County corner records by Highway Department. Distance between Section corners is shown as 5234.76 feet, no location is shown for 1/4 corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-3 (T45N, R1W)  
This corner is being re-established as part of the Chippewa County Remonumentation Program.  
Found no evidence of corner or its accessories. Measured distance between Section corners east and west is 5235.00 feet, distance shown in liber 2, page 220, is 5234.76 feet. Re-established corner by single proportionate measurement on line between Section corners 2617.50 feet east and 2617.50 feet west. North-south position works well with right-of-way fences on 13 Mile Road starting at Highway M-129 and running approximately 800 feet west. Corner falls approximately 100 feet north of east-west gravel road (13 Mile Road).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3 (T45N, R1W)  
Corner is a 3/4" x 24" rebar with 3 1/4" aluminum Chippewa County Remonumentation cap approximately 100 feet north of 13 Mile Road. Witnesses:

- 7" Balsam Fir, N64°E 21.25'
- 6" Balsam Fir, S74°E 24.72'
- 6" Hemlock, S33°E 32.77'
- 5" Balsam Fir, S82°W 8.29'

Note: Distances are to a nail and tag in the side of witness object. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters  
Surveyor's Michigan License No. 33142

Date 10-18-94

