

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa

(County)

Located In:

Corner Code #

- 1. Public Land Survey
 - 1/4 Corner Common: Section Corner Common to:
 - T 45N R 1W
 - T 45N R 1E
 - T 45N R 1W
 - T 45N R 1E
- 2. Property Controlling In Section
 - S T R
 - S T R
- 3. Miscellaneous Property in Sec.
 - S T R
 - S T R

M-12 ✓
A-12
M-11
A-11

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

94 JUL 22 AM 11:12

J. Roger Madsen

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters, in a field survey on NOVEMBER 13, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M-12) GLO Notes: 1/4 Corner midway between sec. cor. From N. Hill, L.L.S., 5-7-91: Fd nail 5.3' West of M-129 c/l, midway & on line between sec.cor. 1/2 mile North and 1/2 mile South. 1992: Neil Hill reset 1/2" iron with cap #27447 (L.7, P.367) N30W 34.48' Tack Top G Post N50W 61.96' MDOT Tag 8" Poplar, S20E 102.45' MDOT Tag 13" Y. Birch, S65W 66.33' MDOT Tag 9" Poplar, S70E 64.79' MDOT Tag 4" Apple, North 2630.27' Sec.Cor., South 2630.27' Sec.Cor

(M-11) From 1965 on LCRC, L.2, P.214: Fd 1" iron pin in monument box. From MDOT Notes 5-01-91: Found 1/2" iron rod in mon. box & witnessed with temp. witnesses. 1992: Neil Hill found 1/2" iron and accepted (L.7, P.367). S75W 77.34' MDOT Tag in Wood G Post, South 82.18' Iron & R/W Cap in Mon. Box, S75E 79.58' Top C/L Conc. R/W Marker N22W 204.39' Top C/L Conc. R/W Marker, N22E 209.41' MDOT Tag Power Pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M-12) Found corner and all accessories as recorded in Liber 7, Page 367 of the Chippewa County Records. Accepted corner position as found.

(M-11) Found corner and all accessories as recorded in Liber 7, Page 367 of the Chippewa County Records. Accepted corner position as found.

SURVEY &
REMONUMENTATION

JUL 26 1994

COMMISSION



- 2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 - (M-12) Corner is a 1/2" rod & cap #27447 in a monument box
 - (M-11) Corner is a 1/2" rod in monument box

WITNESSES

WITNESSES

N 30 W 34.48' Tack Top G Post
 N 50 W 61.96' MDOT Tag 8" Poplar
 S 20 E 102.45' MDOT Tag 13" Y. Birch
 S 65 W 66.33' MDOT Tag 9" Poplar
 S 70 E 64.79' MDOT Tag 4" Apple
 North 2630.27' Section Corner
 South 2630.27' Section Corner

S 75 W 77.34' MDOT Tag in Wood G Post
 South 82.18' Iron & R/W Cap in Mon. Box
 S 75 E 79.58' Top C/L Conc. R/W Marker
 N 22 W 204.39' Top C/L Conc. R/W Marker
 N 22E 209.41' MDOT Tag Power Pole

igned by Keith R. Waters

Date 7-22-94

urveyor's Michigan License No. 33142

NOTE: Bearings are compass bearings corrected for declination.
 Distances are to a nail in side of witness objects unless noted.